





# **Model Curriculum**

**QP Name: BMS Service Engineer** 

QP Code: ELE/Q7104

QP Version: 2.0

**NSQF Level: 5** 

Model Curriculum Version: 2.0

Electronics Sector Skills Council of India || 155, 2nd Floor, ESC House, Okhla Industrial Area - Phase 3, New Delhi – 110020





## **Table of Contents**

Training Parameters
Program Overview5
Training Outcomes5
Compulsory Modules
Module 1: Introduction to the role of a BMS Service Engineer7
Module 2: Process of preparing for installing the BMS
Module 3: Process of carrying out the installation of BMS9
Module 4: Process of carrying out commissioning and testing of BMS11
Module 5: Process of carrying out repair and maintenance of BMS15
Module 6: Basic Health and Safety Practice17
Module 7: Employability Skills (60 Hours)17
Module 8: On-the-Job Training
Annexure
Trainer Requirements
Assessor Requirements
Assessment Strategy20
References
Glossary25
Acronyms and Abbreviations





## **Training Parameters**

Sector	Electronics	
Sub-Sector	Industrial Automation	
Occupation	After Sales Service	
Country	India	
NSQF Level	5	
Aligned to NCO/ISCO/ISIC Code	NCO-2015/7411.0100	
Minimum Educational Qualification and Experience	Pursuing 2nd year of Graduation (B.Sc/B.E./B.Tech) in the relevant field OR Diploma (after 10th (Electronics/ Mechanical/Electrical/Civil)) with 1 Year of relevant experience OR 12th grade pass with 1 year NTC/ NAC with 1 Year of relevant experience OR 12th grade Pass with 2 Years of relevant experience OR Previous relevant Qualification of NSQF Level (4) with 3 Years of relevant experience OR OR	
Pre-Requisite License or Training	NA	
Minimum Job Entry Age	18 Years	
Last Reviewed On	24/02/2022	
Next Review Date	24/02/2025	
NSQC Approval Date	24/02/2022	
QP Version	2.0	
Model Curriculum Creation Date	24/02/2022	
Model Curriculum Valid Up to Date	24/02/2025	
Model Curriculum Version	2.0	

3 | BMS Service Engineer





Maximum Duration of the Course

780 Hours





## **Program Overview**

This section summarizes the end objectives of the program along with its duration.

#### **Training Outcomes**

At the end of the program, the learner should have acquired the listed knowledge and skills:

- Describe the process of preparing for installing the BMS.
- Demonstrate the process of carrying out the installation of BMS.
- Demonstrate the process of carrying out commissioning and testing of BMS.
- Demonstrate the process of carrying out repair and maintenance of BMS.
- Explain the importance of following inclusive practices for all genders and PwD at work.
- Demonstrate various practices to be followed to maintain health and safety at work.

#### **Compulsory Modules**

The table lists the modules and their duration corresponding to the Compulsory NOS of the QP.

NOS and Module Details	Theory Duration	Practical Duration	On-the-Job Training Duration (Mandatory)	On-the-Job Training Duration (Recommended)	Total Duration
Bridge Module	21:00	09:00	00:00	00:00	30:00
Module 1: Introduction to the role of a BMS Service Engineer	21:00	09:00	00:00	00:00	30:00
ELE/N7205 Prepare for installing the BMS	30:00	60:00	30:00	00:00	120:00
Module 2: Process of preparing for installing the BMS	30:00	60:00	30:00	00:00	120:00
ELE/N7206 Carry out the installation of BMS	30:00	60:00	60:00	00:00	150:00
Module 3: Process of carrying out the installation of BMS	30:00	60:00	60:00	00:00	150:00





ELE/N7208 Carry out commissioning and testing of BMS	60:00	60:00	60:00	00:00	180:00
Module 4: Process of carrying out commissioning and testing of BMS	60:00	60:00	60:00	00:00	180:00
ELE/N7207 Carry out repair and maintenance of BMS	60:00	90:00	60:00	00:00	210:00
Module 5: Process of carrying out repair and maintenance of BMS	60:00	90:00	60:00	00:00	210:00
ELE/N1002 Apply health and safety practices at the workplace	15:00	15:00	00:00	00:00	30:00
Module 6: Basic Health and Safety Practice	15:00	15:00	00:00	00:00	30:00
DGT/VSQ/N0102- Employability Skills (60 Hours)	24:00	36:00	00:00	00:00	60:00
Module 7: Employability Skills (60 Hours)	24:00	36:00	00:00	00:00	60:00
Total Duration	240:00	330:00	210:00	00:00	780:00





## **Module Details**

### Module 1: Introduction to the role of a BMS Service Engineer *Bridge Module*

#### **Terminal Outcomes:**

• Discuss the job role of a BMS Service Engineer.

Duration: 21:00	Duration: 09:00
Theory – Key Learning Outcomes	Practical – Key Learning Outcomes
<ul> <li>Describe the size and scope of the Electronics industry and its subsectors.</li> <li>Discuss the role and responsibilities of a BMS Service Engineer.</li> <li>Describe various employment opportunities for a BMS Service Engineer.</li> </ul>	<ul> <li>Awareness of the Tools and Software used in the BMS.</li> <li>Awareness of the Hardware and Automation</li> </ul>
Classroom Aids	
Training Kit - Trainer Guide, Presentations, White	board, Marker, Projector, Laptop
Tools, Equipment and Other Requirements	
NA	





## Module 2: Process of preparing for installing the BMS Mapped to ELE/N7205

#### **Terminal Outcomes:**

- Describe the process of checking the availability of required resources.
- Describe the process of checking and test the received resources.
- Demonstrate the process of preparing for installing the BMS.

Duration: 30:00	Duration: 60:00
Theory – Key Learning Outcomes	Practical – Key Learning Outcomes
<ul> <li>Explain the apparatus required for the installation of BMS such as Direct Digital Controller (DDC), sensors, actuators, relevant types of cables, Human Machine Interface (HMI) display, computer, server, etc.</li> <li>List the necessary tools, equipment, and Personal Protective Equipment (PPE) required for BMS installation.</li> <li>Explain the importance of ensuring that trained personnel assist with the BMS installation process.</li> <li>Describe the process of examining the BMS apparatus before installation to ensure no physical damage or malfunctions.</li> <li>List the applicable documentation requirements.</li> <li>Explain the importance of ensuring all the civil works are completed in the building and necessary approval/ clearance is obtained before starting the installation process.</li> <li>Elabrate how to prepare the circuit diagram/ shop drawing/ as-built drawings for the installation of BMS in the building.</li> <li>Explain the importance of ensuring all the outlets related to BMS are accessible and not covered by Mechanical, Electrical and Plumbing (MEP) services.</li> <li>Explain the importance of ensuring the work area is ready and safe to start the installation of BMS systems.</li> </ul>	<ul> <li>Dramatize how to test the BMS apparatus to ensure the correct functioning.</li> <li>Prepare a sample record of receipt/ replacement and testing of the apparatus.</li> <li>Demonstrate the process of preparing the circuit diagram/ shop drawing/ as-built drawings for the installation of BMS in the building.</li> <li>Demonstrate the process of installing the Heating, Ventilation and Airconditioning HVAC equipment as per the BMS installation plan through coordination with HVAC installation technician.</li> <li>Dramatize how to prepare various equipment for installation as per the manufacturer's instructions.</li> </ul>





 Describe the process of assembling various BMS equipment such as access control, video surveillance, fire alarms, HVAC control, programmable lighting and electric power management for installation.

#### **Classroom Aids**

Training Kit (Trainer Guide, Presentations). Whiteboard, Marker, Projector, Laptop

#### **Tools, Equipment and Other Requirements**

Lighting, Heating, Ventilation and Air Conditioning (HVAC), Fire, Smoke Detection and Alarms, Motion Detectors, CCTV, Security and Access Control, ICT Systems, Lifts, Industrial Processes or Equipment, Shading Devices





## Module 3: Process of carrying out the installation of BMS Mapped to ELE/N7206

#### **Terminal Outcomes:**

- Dramatizee the process of installing conduits and carry out wiring.
- Demonstrate the process of installing the Direct Digital Controller (DDC) with field devices.
- Dramatize the process of installing the central peripherals.
- Demonstrate the process of installing the motion sensors.
- Demonstrate the process of installing the duct air temperature sensor and duct temperature/ humidity sensor.
- Dramatize the process of installing the water differential pressure sensor.
- Demonstrate the process of installing the air differential pressure sensor.
- Demonstrate the process of installing the immersion water temperature sensor.
- Dramatize the process of installing the smoke detectors in AC ducts.
- Demonstrate the process of installing the butterfly valves.

	tical – Key Learning Outcomes Damatize the process of carrying out wiring to connect all the field devices
• Describe the process of installing •	wiring to connect all the field devices
<ul> <li>(PVC)/ (GI) conduits and carry out cabling to connect all the BMS equipment/ devices.</li> <li>Elaborate how to install and terminate the temperature sensor, humidity sensor, motorized damper actuators for HVAC equipment.</li> <li>Elaborate how to install and terminate the CHW temperature sensor, pressure sensor and flow sensors for CHW pipes.</li> <li>Describe the process of connecting all the field devices as per the approved BMS point schedule, wiring schedule and schematic diagrams.</li> <li>Explain how to install the field devices such as outside air humidity sensor, water level sensor as per the approved BMS system.</li> <li>Describe the process of installing the VFDs inside AHU control panels as per the approved schematic diagrams.</li> <li>Describe the process of installing the process of installing conduits and carrying out the wiring</li> </ul>	as per the approved BMS point schedule, wiring schedule and schematic diagrams. Demonstrate the process of installing the control panel with the required power supply at the selected location as per the approved shop drawings. Dramatize the process of installing and terminating the temperature sensor, humidity sensor, motorized damper actuators for HVAC equipment as per the manufacturer's instructions. Demonstrate the process of installing and terminating the CHW temperature sensor, pressure sensor and flow sensors for CHW pipes as per the manufacturer's instructions. Demonstrate the process of installing and connecting the field devices such as outside air humidity sensor, water level sensor, staircase pressurisation sensor as per the approved BMS system Dramatize the process of installing the VFD's inside AHU control panels and making the required cable





DDC panel as per the system requirements.

- Describe the process of carrying out terminations at field ends and control cabling for DDC control panels as per approved shop drawings, schematic drawings.
- Describe the process of installing the central peripherals such as the computer, printer, monitor as per the approved BMS system and shop drawings.
- Describe the process of installing the motion sensors and connecting them for BMS digital control.
- Elaborate how to install the duct air temperature sensor and duct temperature/ humidity sensor.
- Explain how to install the water differential pressure sensor.
- Describe the process of installing an air differential pressure sensor.
- Describe the process of installing an immersion water temperature sensor.
- Elaborate how to install smoke detectors in AC ducts.
- Describe the process of installing butterfly and two-port valves.

connections as per the approved schematic diagrams.

- Demonstrate the process of installing the plumbing system including the water booster pump sets, fire pump sets, water calorifier and pump from the DDC panel, as per the system requirements.
- Demonstrate the process of carrying out control cabling for DDC control panels through GI conduit or GI trunking above the false ceiling as per approved shop drawings, schematic drawings.
- Dramatize the process of installing the pre-assembled peripherals with controllers hubs in the BMS control room.
- Demonstrate the process of carrying out wiring between the central peripherals and the low current systems as per the approved shop drawings.
- Demonstrate the process of installing the central peripherals such as the computer, printer, monitor as per the approved BMS system and shop drawings.
- Demonstrate the process of inserting and installing the duct air temperature sensor and duct temperature/ humidity sensor on the mounting flanges.
- Dramatize the process of installing the water differential pressure sensor below the pressure measuring points using the GI mounting bracket provided with the sensor.
- Demonstrate the process of using the standard fittings supplied with the sensor to make connections.
- Demonstrate the process of installing duct probes in the suction and discharge side of the fans.
- Demonstrate the process of installing the thermowell in the chilled water pipeline and temperature sensor





	<ul> <li>inside the thermowell.</li> <li>Dramatize the process of installing the immersion water temperature sensor as per the approved shop drawings and manufacturer's recommendations.</li> </ul>
	<ul> <li>Demonstrate the process of installing the smoke detector with the base unit inside the smoke chamber using the adopter plates.</li> </ul>
	<ul> <li>Dramatize the process of installing the butterfly valves in a sandwiched position using appropriate flanges.</li> </ul>
	<ul> <li>Demonstrate the process of installing actuators after installing and insulating the valves.</li> </ul>
Classroom Aids	
Training Kit (Trainer Guide, Presentations). White	eboard, Marker, Projector, Laptop
Tools, Equipment and Other Requirements	
Lighting, Heating, Ventilation and Air Conditionin Motion Detectors, CCTV, Security and Access Cor Equipment, Shading Devices	





## Module 4: Process of carrying out commissioning and testing of BMS Mapped to ELE/N7208

#### **Terminal Outcomes:**

- Demonstrate the process of carrying out pre-commissioning of BMS.
- Demonstrate the process of carrying out commissioning of DDC panels.
- Demonstrate the process of carrying out commissioning of the Fan Coil Unit (FCU).
- Dramatize the process of testing the digital and analogue inputs and outputs.
- Dramatize the process of testing the communication link, printer and alarms.
- Dramatize the process of testing the third-party system interface connectivity.

Duration: 60:00	Duration: 60:00
Theory – Key Learning Outcomes	Practical – Key Learning Outcomes
<ul> <li>Describe the process of pre- commissioning a BMS.</li> <li>Explain the importance of ensuring</li> </ul>	<ul> <li>Dramatize how to replace any damaged components as per the SOP.</li> </ul>
that all peripheral devices are mounted and connected.	<ul> <li>Demonstrate the process of testing all control cables point to point using a multimeter.</li> </ul>
<ul> <li>Explain the importance of checking the mechanical installations for the correct location and application.</li> </ul>	<ul> <li>Demonstrate the process of installing the DDC controller software for</li> </ul>
<ul> <li>Elaborate how to check if all the cables are connected correctly inside the control panels/ DDC controllers</li> </ul>	correct automation of DDC, as per the instructions included with the licensed software.
<ul> <li>and to the peripheral devices.</li> <li>Describe the process of checking the control panel input terminals for</li> </ul>	<ul> <li>Dramatize how to set the controller address, date and time and check for any system alarms.</li> </ul>
interference voltages with the use of an AC range voltmeter.	• Dramatize how to connect the field wiring at DDC controller.
<ul> <li>Elaborate how to check if the Fan Coil Unit (FCU) controllers are installed and connected via the communication bus.</li> </ul>	• Demonstrate the process of testing that changes occur in field as per the sequence of operation.
<ul> <li>Explain the importance of ensuring the installation of all the sensors, DP switches, valves are completed both mechanically and electrically.</li> </ul>	<ul> <li>Dramatize how to connect each pair of field instrument cable at the appropriate terminals as per the panel wiring termination drawing.</li> </ul>
• Elaborate the use of a multimeter to test all control cables.	<ul> <li>Dramatize how to shorten and disconnect the wires at the field end and check for appropriate LED status</li> </ul>
<ul> <li>Describe the process of commissioning DDC panels including the installation of relevant DDC controller application software.</li> </ul>	<ul> <li>at the DI module.</li> <li>Demonstrate the process of changing the Hand-Off-Auto selector switches for all the equipment to auto position.</li> </ul>
<ul> <li>Describe the process of testing the digital input/ output and analogue</li> </ul>	<ul> <li>Dramatize how to connect all cables</li> </ul>





input/ output.

- Describe the process of commissioning the Fan Coil Unit (FCU).
- Explain the importance of checking the network communication between the BMS servers, workstations, DDC Panels, LON to IP converters (LIP) and Building Automation and Control Network (BACnet) controllers.
- Describe the process of testing the sequence of operation according to changes in the field devices.
- Describe the process of checking the printer and alarms for the correct functioning.
- Elaborate how to check that the communication link is up between the servers/ workstations and printers.
- Elaborate how to check the thirdparty system interface connectivity.

of field instruments for analogue inputs/ outputs at the appropriate terminals as per the panel wiring termination drawing.

- Demonstrate how to connect all cables of field instruments for analogue inputs/ outputs at the appropriate terminals as per the panel wiring termination drawing.
- Dramatize how to test each alarm in the system and validate that the system generates the appropriate alarm message, the message appears at workstations and printers, and any other related actions occur as defined.
- Demonstrate how to check and verify the sequence of operations according to the Sequence of Operation Manual after all field cables are verified and checked.

#### **Classroom Aids**

Training Kit (Trainer Guide, Presentations). Whiteboard, Marker, Projector, Laptop

#### **Tools, Equipment and Other Requirements**

Lighting, Heating, Ventilation and Air Conditioning (HVAC), Fire, Smoke Detection and Alarms, Motion Detectors, CCTV, Security and Access Control, ICT Systems, Lifts, Industrial Processes or Equipment, Shading Devices





## Module 5: Process of carrying out repair and maintenance of BMS Mapped to ELE/N7207

#### **Terminal Outcomes:**

- Demonstrate the process of carrying out repair and maintenance of BMS field devices.
- Dramatize the process of carrying out repair and maintenance of electrical panels.
- Describe the process of managing the BMS helpdesk, complaints and requests.
- Demonstrate the process of maintaining the records.

Duration: 60:00	Duration: 90:00
Theory – Key Learning Outcomes	Practical – Key Learning Outcomes
<ul> <li>Describe the process of testing the valve actuators, damper actuator, sensors, transducers, high-low limit thermostats, frost thermostats, pressure switches, control valve, relays, emergency stop button and fire/ smoke shut-down, the shut-off operation of spring return actuators and Digital Input and Output (I/O) for the correct functioning.</li> </ul>	<ul> <li>Demonstrate the process of testing the valve actuators, damper actuator, sensors, transducers, high-low limit thermostats, frost thermostats, pressure switches, control valve, etc. for correct functioning.</li> <li>Dramatize how to clean the valve actuators, damper actuators and sensors.</li> </ul>
• Explain the importance of ensuring the field devices are not worn out or damaged.	<ul> <li>Demonstrate how to re-calibrate all sensors, transducers, valve start points and actuator travel times as per the requirement.</li> </ul>
• Elaborate how to check the BMS is connected with the control system and is online.	<ul> <li>Demonstrate how to replace the worn-out or damaged field devices as per the Standard Operating</li> </ul>
<ul> <li>Elaborate how to identify the repair and maintenance needs of the BMS control system.</li> <li>Elaborate how to check if the motion</li> </ul>	<ul> <li>Procedure.</li> <li>Dramatize the process of carrying out maintenance of the motion sensors or replace them as required.</li> </ul>
<ul> <li>Elaborate now to check if the motion sensors are working as expected and replacing them if required.</li> <li>Describe the process of cleaning the</li> </ul>	<ul> <li>Demonstrate the process of carrying out control panel modifications, up- gradation and installations as</li> </ul>
<ul><li>valve actuators, damper actuators and sensors.</li><li>Describe the process of re-calibrating</li></ul>	<ul> <li>required.</li> <li>Dramatize the process of maintaining the logs of calls reporting any issues</li> </ul>
all sensors, transducers, valve start points and actuator travel times.	<ul><li>with the BMS.</li><li>Dramatize the process of maintaining</li></ul>
<ul> <li>Describe the process of replacing the worn out or damaged field devices.</li> <li>Explain how to check settings, ratings</li> </ul>	and update documents related to BMS room, device hosting and its maintenance.
and operation of protective devices such as overloads, residual current devices, circuit breakers and fuses.	<ul> <li>Dramatize the process of maintaining records and logs regarding the building temperatures, energy consumption, control panel readings,</li> </ul>





- Elaborate signs of overheating of components such as contactors, cables, connectors and internal temperature within the electrical panels.
- Describe the process of re-torqueing the busbar nuts and bolts.
- Elaborate how to check if the electrical panel is earth-bonded correctly.
- Elaborate how to check if the main door electrical isolator is engaged and operational.
- Explain the importance of ensuring ventilation fans and grilles are functional and clean.
- Explain the importance of ensuring isolators, relays, contactors and starters are functioning correctly and free from pitting.
- Explain the importance of ensuring incoming power supply voltages are within the prescribed limits.
- Explain the importance of ensuring status indicators on all panels are functional.
- Explain the importance of ensuring the closure of BMS-related requests/ complaints with timely resolution.
- Explain the importance of directing the BMS complaints requiring vendor attention to the concerned vendor promptly and escalating the unresolved complaints to the relevant authority as per the escalation matrix.
- List various records to be maintained regarding the BMS operations.

**Classroom Aids** 

Training Kit (Trainer Guide, Presentations). Whiteboard, Marker, Projector, Laptop

#### **Tools, Equipment and Other Requirements**

Lighting, Heating, Ventilation and Air Conditioning (HVAC), Fire, Smoke Detection and Alarms, Motion Detectors, CCTV, Security and Access Control, ICT Systems, Lifts, Industrial Processes or Equipment, Shading Devices

issues encountered and the steps taken to correct the problem, etc.

 Prepare a sample daily/ weekly/ monthly Management Information Systems (MIS) report regarding the requests/ complaints received.





### Module 6: Basic Health and Safety Practice Mapped to ELE/N1002

#### **Terminal Outcomes:**

• Apply health and safety practices at the workplace.

Duration: 15:00	Duration: 15:00
Theory – Key Learning Outcomes	Practical – Key Learning Outcomes
<ul> <li>List the types of fire and fire</li> </ul>	• Demonstrate the correct method of
<ul> <li>List the common sources of pollution and ways to minimize it.</li> </ul>	
<ul> <li>Describe the concept of waste management and methods of disposing hazardous waste.</li> </ul>	
<ul> <li>Explain various warning and safety signs.</li> </ul>	
<ul> <li>Describe different ways of preventing accidents at the workplace.</li> </ul>	





#### **Classroom Aids**

Training Kit (Trainer Guide, Presentations). Whiteboard, Marker, Projector, Laptop

#### **Tools, Equipment and Other Requirements**

Personal Protection Equipment: Safety Glasses, Head Protection, Rubber Gloves, Safety Footwear, Warning Signs and Tapes, Fire Extinguisher, First Aid Kit, Fire Extinguishers and Warning Signs.





### Module 7: Employability Skills (60 Hours) Mapped to DGT/VSQ/N0102

#### Terminal Outcomes:

- Discuss about Employability Skills in meeting the job requirements
- Describe opportunities as an entrepreneur.
- Describe ways of preparing for apprenticeship & Jobs appropriately.

Duration: 24:00	Duration: 36:00
Theory – Key Learning Outcomes	Practical – Key Learning Outcomes
<ul> <li>Explain constitutional values, civic rights, responsibility towards society to become a responsible citizen</li> </ul>	<ul> <li>List different learning and employability related GOI and private portals and their usage</li> </ul>
<ul> <li>Discuss 21<sup>st</sup> century skills</li> <li>Explain use of basic English phrases and sentences.</li> </ul>	<ul> <li>Show how to practice different environmentally sustainable practices.</li> <li>Exhibit 21st century skills like Self-</li> </ul>
<ul> <li>Demonstrate how to communicate in a well-behaved manner</li> </ul>	Awareness, Behavior Skills, time management, etc.
<ul> <li>Demonstrate how to work with others</li> </ul>	• Show how to use basic English sentences f everyday conversation in different contex
<ul> <li>Demonstrate how to operate digital devices</li> </ul>	<ul> <li>in person and over the telephone</li> <li>Demonstrate how to communicate in a we -mannered way with others.</li> </ul>
<ul> <li>Discuss the significance of Internet and Computer/ Laptops</li> </ul>	<ul> <li>Demonstrate how to communicate effectively using verbal and</li> </ul>
<ul> <li>Discuss the need for identifying business opportunities</li> </ul>	<ul> <li>Output the structure of the str</li></ul>
• Discuss about types of customers.	effectively
<ul> <li>Discuss on creation of biodata</li> <li>Discuss about apprenticeship and opportunities related to it.</li> </ul>	<ul> <li>Demonstrate how to maintain hygiene and dressing appropriately.</li> <li>Perform a mock interview</li> </ul>

#### **Classroom Aids**

Training Kit (Trainer Guide, Presentations). Whiteboard, Marker, Projector, Laptop

#### **Tools, Equipment and Other Requirements**

Computer, UPS, Scanner, Computer Tables, LCD Projector, Computer Chairs, White Board

OR

Computer Lab





### Module 8: On-the-Job Training

Mapped to BMS Service Engineer

Mandatory Duration: 210:00		Recommended Duration: 00:00			
Location: On Site					
Ter	minal Outcomes				
1.	Explain the process of preparing for installing	the BMS.			
2.	Install conduits and carry out wiring				
3.	Install the Direct Digital Controller (DDC) with	n field devices			
4.	Install the central peripherals and motion ser	nsors			
5.	Install the duct air temperature sensor and duct temperature/ humidity sensor				
6.	Install the water and air differential pressure sensor				
7.	Install the immersion water temperature sensor				
8.	Install the smoke detectors in AC ducts				
9.	Install the butterfly valves				
10.	Carry out pre-commissioning of BMS				
11.	··· / ···· 0· ····				
12.	Test the digital and analogue inputs and outp	outs			
13.	Test the communication link, printer and alar	ms			
14.	Test the third-party system interface connect	tivity			
15.	Carry out repair and maintenance of BMS fiel	ld devices and electrical panels			
16.	Use professional language and behaviour tha	t is respectful of PwD and all genders.			
17.	Use protective equipment suitable as per tas	ks and work conditions.			





## Annexure

## **Trainer Requirements**

Trainer Prerequisites						
Minimum Educational	ational		Relevant Industry Experience		ng ience	Remarks
Qualification		Years	Specialization	Years	Specialization	
Diploma/	(Electrical/Electronics/	2	BMS Service	1	Electronics	
Degree/ ITI/	Industrial		Engineering/	_		
Certified in	Automation/		Building			
relevant CITS	Mechanical)		Automation			
Trade						

Trainer Certification			
Domain Certification	Platform Certification		
"BMS Service Engineer", "ELE/Q7104, v2.0", Minimum accepted score is 80%	Recommended that the Trainer is certified for the <b>BMS Service Engineer</b> "Trainer (VET and Skills)", mapped to the Qualification Pack: "MEP/Q2601, V2.0", with minimum score of 80%		





## **Assessor Requirements**

Assessor Prerequisites						
Minimum Educational	Specialization	Relevant Industry Experience		Training/Assessment Experience		Remarks
Qualification		Years	Specialization	Years	Specialization	
Diploma/ Degree/ ITI/ Certified in relevant CITS Trade	(Electrical/Electronics/ Industrial Automation/ Mechanical)	3	BMS Service Engineering/ Building Automation	1	Electronics	

Assessor Certification			
Domain Certification	Platform Certification		
" <b>BMS Service Engineer</b> ", "ELE/Q7104, v2.0", Minimum accepted score is 80%	Recommended that the Assessor is certified for the <b>BMS Service Engineer</b> "Assessor (VET and Skills)", mapped to the Qualification Pack: "MEP/Q2701, V2.0", with minimum score of 80%		





### **Assessment Strategy**

- 1. Assessment System Overview:
  - Batches assigned to the assessment agencies for conducting the assessment on SDMS/SIP or email
  - Assessment agencies send the assessment confirmation to VTP/TC looping SSC
  - The assessment agency deploys the ToA certified Assessor for executing the assessment
  - SSC monitors the assessment process & records
- 2. Testing Environment

To ensure a conducive environment for conducting a test, the trainer will:

- Confirm that the centre is available at the same address as mentioned on SDMS or SIP
- Check the duration of the training.
- Check the Assessment Start and End time to be 10 a.m. and 5 p.m. respectively
- Ensure there are 2 Assessors if the batch size is more than 30.
- Check that the allotted time to the candidates to complete Theory & Practical Assessment is correct.
- Check the mode of assessment—Online (TAB/Computer) or Offline (OMR/PP).
- Confirm the number of TABs on the ground are correct to execute the Assessment smoothly.
- Check the availability of the Lab Equipment for the particular Job Role.
- 3. Assessment Quality Assurance levels / Framework:
  - Question papers created by the Subject Matter Experts (SME)
  - Question papers created by the SME verified by the other subject Matter Experts
  - Questions are mapped with NOS and PC
  - Question papers are prepared considering that level 1 to 3 are for the unskilled & semiskilled individuals, and level 4 and above are for the skilled, supervisor & higher management
  - The assessor must be ToA certified and the trainer must be ToT Certified
  - The assessment agency must follow the assessment guidelines to conduct the assessment
- 4. Types of evidence or evidence-gathering protocol:
  - Time-stamped & geotagged reporting of the assessor from assessment location
  - Centre photographs with signboards and scheme-specific branding
  - Biometric or manual attendance sheet (stamped by TP) of the trainees during the training period
  - Time-stamped & geotagged assessment (Theory + Viva + Practical) photographs & videos
- 5. Method of verification or validation:

To verify the details submitted by the training centre, the assessor will undertake:

- A surprise visit to the assessment location
- A random audit of the batch
- A random audit of any candidate
- 6. Method for assessment documentation, archiving, and access

To protect the assessment papers and information, the assessor will ensure:

• Hard copies of the documents are stored





- Soft copies of the documents & photographs of the assessment are uploaded / accessed from Cloud Storage
- Soft copies of the documents & photographs of the assessment are stored on the Hard drive





## References

## Glossary

Term	Description
Declarative knowledge	Declarative knowledge refers to facts, concepts and principles that need to be known and/or understood in order to accomplish a task or to solve a problem.
Key Learning	Key learning outcome is the statement of what a learner needs to know, understand and be able to do in order to achieve the terminal outcomes. A set of key learning outcomes will make up the training outcomes. Training outcome is specified in terms of knowledge, understanding (theory) and skills (practical application).
(M) TLO	On-the-job training (Mandatory); trainees are mandated to complete specified hours of training on site
OJT (R)	On-the-job training (Recommended); trainees are recommended the specified hours of training on site
Procedural Knowledge	Procedural knowledge addresses how to do something, or how to perform a
Training Outcome	Training outcome is a statement of what a learner will know, understand and be able to do <b>upon the completion of the training</b> .
Terminal Outcome	Terminal outcome is a statement of what a learner will know, understand and be able to do <b>upon the completion of a module.</b> A set of terminal outcomes help to achieve the training outcome.





### **Acronyms and Abbreviations**

Term	Description
BMS	Building Management System
ISO	International Organization for Standardization
NCO	National Occupational Standards
NOS	National Skills Qualification Committee
NSQF	National Skills Qualification Framework
ΤΙΟ	On-the-Job Training
OMR	Optical Mark Recognition
РС	Performance Criteria
PwD	Persons with Disabilities
QP	Qualification Pack
SDMS	Skill Development & Management System
SIP	Skill India Portal
SME	Small and Medium Enterprises
SOP	Standard Operating Procedure
SSC	Sector Skill Council
тс	Trainer Certificate
ТоА	Training of Assessors
ТоТ	Training of Trainers
ТР	Training Provider